

Page 27 has been amended as follows:

PART 3- EXECUTION

3.1 EXISTING MEMBRANE REMOVAL

- A. REMOVE ALL GRAVEL BALLAST WHERE OCCURS AND SMOOTH THE REMAINING TAR LAYER SUFFICIENTLY TO REMOVE BLISTERS AND ALL UNEVEN IMPERFECTIONS THAT WOULD CAUSE THE COVER BOARD TO NOT LAY FLAT AND UNIFORM.
- B. REMOVE MODIFIED BITUMEN ROOFING SHEETS, ALL LAYERS WHERE OCCUR AND SMOOTH EXISTING SUBSTRATE ADEQUATELY TO ACCEPT THE COVER BOARD.
- C. REMOVE AND REPLACE ALL MEMBRANE FLASHINGS INCLUDING METAL FLASHINGS AND COPINGS ~~AS REQUIRED TO REMOVE AND~~ TO PROPERLY INSTALL THE NEW MEMBRANE ROOF.
- D. ALL SHEET METAL COPINGS SHALL BE REPLACED WITH SAME GAUGE, FINISH AND COLOR AS EXISTING.
- E. ~~ROOF DRAIN DOMES AND FLASHING COLLARS/CLAMPING RINGS REMOVED SHALL BE REPLACED WITH NEW NON-CORROSIVE UNITS OF SAME SIZE AND TYPE.~~

ROOF DRAIN SHALL BE REMOVED TO THE EXISTING DRAINPIPE AND REPLACED WITH NEW NON-CORROSIVE METAL UNITS OF SAME SIZE AND TYPE.

- F. CERTAIN EXISTING ROOF CURBS AS IDENTIFIED BY COUNTY PERSONNEL SHALL BE REMOVED ~~OR CAPPED. BIDS SHALL IDENTIFY THE BIDDERS PREFERENCE AND PROVIDE PRICING FOR BOTH METHODS. IF CURB IS TO BE REMOVED, THE OPENING SHALL BE PATCHED WITH SAME ROOF CONSTRUCTION AS ADJACENT. IF CURBS ARE TO BE CAPPED, THE CAP SHALL INCORPORATE A SOLID SUBSTRATE WITH SUFFICIENT STRENGTH TO SPAN THE OPENING, A 2" RIGID INSULATION BOARD, AND A WATERTIGHT SHEET METAL CAP.~~
- G. CONTRACTOR SHALL COORDINATE WITH COUNTY PERSONNEL AND TEMPORARILY RAISE ALL CONDUITS AND GAS PIPING AS REQUIRED FOR THE NEW WORK. AFTER COMPLETION OF THE WORK CONTRACTOR SHALL PROVIDE PLASTIC SUPPORTS FOR ALL CONDUITS AND PIPING OF SIZE, TYPE AND STRENGTH AS RECOMMENDED AND APPROVED BY THE MEMBRANE MANUFACTURER.

Signature of Bidder: _____